



Address: 629 Brook Meadow Dr. Ballwin MO 63021

Call us: +1 (302) 440-3753

E-mail: mike@smaestimating.com

Website: www.smaestimating.com

SAN DIEGO HIGH SCHOOL

1405 PARK BLVD. SAN DIEGO. CA 92101

OWNER

ARCHITECT

ADDENDA

Addendum Issued: NONE

Please review any Addendum issued after Date
07/08/21

ID: -1301

BIDDER NAME: _____



S#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	LABOR			MATERIAL (\$Per Unit)	EQUIPMENT (\$Per Unit)	COMPOSITE RATE/UNIT	TOTAL COST
							MHrs/ Unit	\$/Hour	(\$Per Unit)				
			010000	DIVISION 01 - GENERAL REQUIREMENTS									
1				MOBILIZATION	1	LS							
2				BOND & INSURANCE	1	LS							
3				SUPERVISION	1	LS							
4				SUBMITTALS & SAMPLES	1	LS							
5				TEMPORARY FACILITIES & CONTROLS	1	LS							
6				PROJECT SCHEDULE	1	LS							
7				CLOSEOUT PROCEDURES	1	LS							
8				PERMITS	1	LS							
				Subtotal									
				SITEWORK									
			020000	DIVISION 02 - EXISTING CONDITIONS									
			022000	EARTHWORK									
9	C-141			Footing excavation.	248.66	CY							
10				Footing backfill.	225.90	CY							
			025130	SIDEWALK AND STREET PAVING									
				(4" THK) CONCRETE SIDEWALK									
11				Compaction of subgrade.	90250	SF							
12	C-112 to	C-501		(8" THK) Subgrade.	2226.05	CY							
13	C-117			(4" THK) Base.	1113.03	CY							
14				Rebar's (Grade 60)	67.88	TON							
15				(4" THK) Concrete sidewalk. (fc = 4000 PSI)	1252.30	CY							
				(8" THK) CONCRETE APRON									
16				Compaction of subgrade.	20305	SF							
17	C-113	C-501		(8" THK) Subgrade.	500.88	CY							
18				(4" THK) Base.	500.88	CY							
19				Rebar's (Grade 60)	15.23	TON							
20				(8" THK) Concrete apron. (fc = 4000 PSI)	532.22	CY							
			025210	CONCRETE CURBS AND PAVEMENTS									
				CONCRETE CURBS & GUTTER									
21				Compaction of subgrade.	12210	SF							
22	C-112 to	C-501		Rebar's (Grade 60)	5.87	TON							
23	C-117			(6"x11"Wx15"H) Concrete curb. (fc = 4000 PSI)	123.32	CY							
24				(6"Wx15"H) Concrete curb. (fc = 4000 PSI)	132.57	CY							
25				(2"Wx6"H) Concrete gutter. (fc = 4000 PSI)	31.93	CY							
				Subtotal									
			030000	DIVISION 03 - CONCRETE									
			033000	CAST IN PLACE CONCRETE									
				(3'6"Wx1'H) CONCRETE BENCH FOOTING									
26	AS-110 to	B3 & C3		Compaction of sub-grade.	1480	SF							
27	AS-129	/AS-513		Rebar's (Grade 60)	1.03	TON							
28				Concrete footing. (fc = 4000 PSI)	54.98	CY							
				(2'Wx1'H) CONCRETE QUAD SEAT FOOTING									
29	AS-110 to	D1/AS-506 &		Compaction of sub-grade.	990	SF							
30	AS-129	C1/AS-507		Rebar's (Grade 60)	0.63	TON							
31				Concrete footing. (fc = 4000 PSI)	33.65	CY							
				(10"Wx1'4"H) STAIR CONCRETE FOOTING									
32	AS-110 to	B1/AS-507		Compaction of sub-grade.	65	SF							
33	AS-129			Rebar's (Grade 60)	0.04	TON							
34				Concrete footing. (fc = 4000 PSI)	2.14	CY							
				(2'6"Wx2'10"H) CONCRETE BENCH									
35	AS-110 to	A3/AS-513		Compaction of sub-grade.	1255	SF							
36	AS-129			Rebar's (Grade 60)	2.59	TON							
37				Concrete bench. (fc = 4000 PSI)	126.08	CY							
				(6"THKx1'8"H) CONCRETE BENCH WALL									
38	AS-110 to	C3/AS-513		Rebar's (Grade 60)	0.07	TON							
39	AS-129			Concrete bench wall. (fc = 4000 PSI)	3.06	CY							
				(7"THKx1'8"H) CONCRETE BENCH WALL									
40	AS-110 to	B3/AS-513		Rebar's (Grade 60)	0.49	TON							
41	AS-129			Concrete bench wall. (fc = 4000 PSI)	21.87	CY							
				(8"THKx1'8"H) CONCRETE BENCH WALL									
42	AS-110 to	D3/AS-513		Rebar's (Grade 60)	0.12	TON							
43	AS-129			Concrete bench wall. (fc = 4000 PSI)	5.50	CY							
				(6"THKx1'H) CONCRETE QUAD SEAT WALL									
44	AS-115	C1/AS-507		Rebar's (Grade 60)	0.02	TON							
45				Concrete quad seat wall. (fc = 4000 PSI)	0.93	CY							
				(6"THKx1'8"H) CONCRETE QUAD SEAT WALL									
46	AS-115	C1/AS-507		Rebar's (Grade 60)	0.03	TON							
47				Concrete quad seat wall. (fc = 4000 PSI)	1.56	CY							
				(6"THKx2'3"H) CONCRETE QUAD SEAT WALL									
48	AS-115	C1/AS-507		Rebar's (Grade 60)	0.05	TON							
49				Concrete quad seat wall. (fc = 4000 PSI)	2.17	CY							
				(8"THKx2'H) CONCRETE QUAD SEAT WALL									
50	AS-115	D1/AS-506		Rebar's (Grade 60)	0.19	TON							
51				Concrete quad seat wall. (fc = 4000 PSI)	8.41	CY							
				(8"THKx4'H) CONCRETE QUAD SEAT WALL									
52	AS-115	D1/AS-506		Rebar's (Grade 60)	0.40	TON							
53				Concrete quad seat wall. (fc = 4000 PSI)	17.87	CY							
				CONCRETE SEATS SLAB									
54	AS-110 to	D1/AS-506,		Rebar's (Grade 60)	1.91	TON							
55	AS-129	C1/AS-507 &		Concrete quad seat wall. (fc = 4000 PSI)	8.10	CY							
56		B3 & C3		Concrete quad seat wall. (fc = 4000 PSI)	32.63	CY							
57		/AS-513		Concrete quad seat wall. (fc = 4000 PSI)	26.19	CY							
				(6" THK) CONCRETE BACKFLOW PREVENTION PAD									
58	C-141			Compaction of sub-grade.	65	SF							
59				Rebar's (Grade 60)	0.03	TON							
60				Concrete footing. (fc = 4000 PSI)	1.37	CY							
				(6" THK) CONCRETE STAIRS									
61	C-112 &			Compaction of sub-grade.	1760	SF							
62	C-113			Rebar's (Grade 60)	4.40	TON							
63				Concrete stair. (fc = 4000 PSI)	70.65	CY							
				Subtotal									
				BUILDING 100									
			020000	DIVISION 02 - EXISTING CONDITIONS									
			022000	EARTHWORK									
64	S1-101			Footing excavation.	566.35	CY							
65				Footing backfill.	283.22	CY							
				Subtotal									
			030000	DIVISION 03 - CONCRETE									
			033000	CAST IN PLACE CONCRETE									
				(1'Wx1'6"H) CONCRETE FOOTING									
66	S1-101	D4/SS-501		Compaction of sub-grade.	1210	SF							
67				Rebar's (Grade 60)	0.965	TON							
68				Concrete footing. (fc = 4000 PSI)	51.39	CY							
				(2'Wx1'6"H) CONCRETE FOOTING									
69	S1-101	D1/S-003		Compaction of sub-grade.	105	SF							
70				Rebar's (Grade 60)	0.100	TON							
71				Concrete footing. (fc = 4000 PSI)	5.30	CY							
				(2'6"Wx1'2"H) CONCRETE FOOTING									
72	S1-101	D4/S1-502		Compaction of sub-grade.	20	SF							
73				Rebar's (Grade 60)	0.014	TON							
74				Concrete footing. (fc = 4000 PSI)	0.74	CY							

S#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY	UNIT	MHrs/ Unit	LABOR \$/Hour (\$Per Unit)	MATERIAL (\$Per Unit)	EQUIPMENT (\$Per Unit)	COMPOSITE RATE/UNIT	TOTAL COST
75	S1-101	A3/S1-507		(3'Wx3'H) CONCRETE FOOTING								
76			Compaction of sub-grade.	195	SF							
77			Rebar's (Grade 60)	0.398	TON							
				Concrete footing. (fc = 4000 PSI)	21.21	CY						
78	S1-101	1/S1-403		(4'Wx2'H) CONCRETE FOOTING								
79			Compaction of sub-grade.	195	SF							
80			Rebar's (Grade 60)	0.434	TON							
				Concrete footing. (fc = 4000 PSI)	23.10	CY						
81	S1-101	B4/S1-506		(6'6"Wx2'H) CONCRETE FOOTING								
82			Compaction of sub-grade.	140	SF							
83			Rebar's (Grade 60)	0.226	TON							
				Concrete footing. (fc = 4000 PSI)	11.04	CY						
84	S1-101	B1/SS-501 & D1-SS-501		(7'Wx2'H) CONCRETE FOOTING								
85			Compaction of sub-grade.	495	SF							
86			Rebar's (Grade 60)	0.804	TON							
87			Concrete footing. (fc = 4000 PSI)	39.18	CY							
				(3/4"DIAx16"H) EMBEDDED STEEL ROD	24.00	EA						
88	S1-101	D4/S1-502		(10"12"Wx8"H) THICKEND EDGE CONCRETE SLAB FOOTING								
89			Compaction of sub-grade.	165	SF							
90			Rebar's (Grade 60)	0.063	TON							
				Concrete footing. (fc = 4000 PSI)	3.36	CY						
91	S1-101	D3/S-009		(1'6"Wx2'H) THICKEND EDGE CONCRETE SLAB FOOTING								
92			Compaction of sub-grade.	35	SF							
93			Rebar's (Grade 60)	0.043	TON							
				Concrete footing. (fc = 4000 PSI)	2.27	CY						
94	S1-101	B5/S1-502		(1'6"1'10"Wx8"H) THICKEND EDGE CONCRETE SLAB FOOTING								
95			Compaction of sub-grade.	16	SF							
96			Rebar's (Grade 60)	0.006	TON							
				Concrete footing. (fc = 4000 PSI)	0.35	CY						
97	S1-101	B1/SS-501 & D1-SS-501		(1'5'2"Wx1'H) THICKEND EDGE CONCRETE SLAB FOOTING								
98			Compaction of sub-grade.	310	SF							
99			Rebar's (Grade 60)	0.193	TON							
				Concrete footing. (fc = 4000 PSI)	10.30	CY						
100	S1-101	B3/S1-505		(12'Wx3'H) CONCRETE GRADE BEAM								
101			Compaction of sub-grade.	470	SF							
102			Rebar's (Grade 60)	1.320	TON							
103			Concrete footing. (fc = 4000 PSI)	57.47	CY							
				(2"DIAx30"H) EMBEDDED STEEL ROD	16.00	EA						
104	S1-101	1 & 4/S1-403		(1'3"Wx3'H) CONCRETE PEDESTAL								
105			Compaction of sub-grade.	155	SF							
106			Rebar's (Grade 60)	0.279	TON							
				Concrete footing. (fc = 4000 PSI)	14.01	CY						
107	S1-101	D5/S-007		(3' SQ.x1'6"H) CONCRETE FOOTING PAD (5 EA)								
108			Compaction of sub-grade.	65	SF							
109			Rebar's (Grade 60)	0.054	TON							
110			Concrete footing. (fc = 4000 PSI)	2.88	CY							
				(3/4"DIAx15"H) EMBEDDED STEEL ROD	20.00	EA						
111	S1-101	B3/S1-502		(4' SQ.x1'6"H) CONCRETE FOOTING PAD (1 EA)								
112			Compaction of sub-grade.	20	SF							
113			Rebar's (Grade 60)	0.019	TON							
114			Concrete footing. (fc = 4000 PSI)	1.02	CY							
				(3/4"DIAx15"H) EMBEDDED STEEL ROD	4.00	EA						
115	S1-101	D1/S-003		(5' SQ.x2'H) CONCRETE FOOTING PAD (1 EA)								
116			Compaction of sub-grade.	30	SF							
117			Rebar's (Grade 60)	0.056	TON							
118			Concrete footing. (fc = 4000 PSI)	2.13	CY							
				(3/4"DIAx15"H) EMBEDDED STEEL ROD	4.00	EA						
119	S1-101	B4/S1-506		(5'Wx6'Lx2'H) CONCRETE FOOTING PAD (1 EA)								
120			Compaction of sub-grade.	40	SF							
121			Rebar's (Grade 60)	0.068	TON							
122			Concrete footing. (fc = 4000 PSI)	2.56	CY							
				(3/4"DIAx15"H) EMBEDDED STEEL ROD	8.00	EA						
123	S1-101	A4/S1-502 & A2/S1-506		(8'8"Wx9'7"Lx1'2"H) ELEVATOR CONCRETE FOOTING PAD (1 EA)								
124			Compaction of sub-grade.	95	SF							
125			Rebar's (Grade 60)	0.109	TON							
126			Concrete footing. (fc = 4000 PSI)	4.12	CY							
				(5/8"DIAx12"H) EMBEDDED STEEL ROD	8.00	EA						
127	S1-101	1 & 4/S1-403, D3/S1-501, B2/S1-507, B1/SS-501 & D1-SS-501		RETAINING WALL								
128			Rebar's (Grade 60)	1.850	TON							
129			(6" THK) Retaining wall. (fc = 4000 PSI)	26.21	CY							
130			(8" THK) Retaining wall. (fc = 4000 PSI)	3.53	CY							
131			(10" THK) Retaining wall. (fc = 4000 PSI)	12.75	CY							
132			(12" THK) Retaining wall. (fc = 4000 PSI)	8.29	CY							
133			(18" THK) Retaining wall. (fc = 4000 PSI)	22.42	CY							
			KEYWAY	153.07	LF							
134	S1-101 & S-403	A2/S1-506		SHOTCRETE WALL								
135			Rebar's (Grade 60)	0.780	TON							
136			(6" THK) Concrete shotcrete wall. (fc = 4000 PSI)	26.85	CY							
				(8" THK) Concrete shotcrete wall. (fc = 4000 PSI)	2.73	CY						
137	S1-101	S-002		SLAB ON GRADE								
138			Compaction of subgrade.	1830	SF							
139			Vapor barrier.	1830	SF							
140			(4" THK) Aggregate base.	22.56	CY							
141			Rebar's (Grade 60)	1.37	TON							
				(5" THK) Concrete slab on grade. (fc = 4000 PSI)	31.01	CY						
142	S1-101	S-002		SLAB ON GRADE								
143			Compaction of subgrade.	45	SF							
144			Vapor barrier.	45	SF							
145			(4" THK) Aggregate base.	0.54	CY							
146			Rebar's (Grade 60)	0.03	TON							
				(6" THK) Concrete slab on grade. (fc = 4000 PSI)	0.74	CY						
147	S1-102	3/S1-404 & C3/S1-506		LIGHT WEIGHT CONCRETE SLAB								
148			(2" THK) LIGHT WEIGHT CONCRETE W/ CIP 6x6 - W4xW4 WWF	2.78	CY							
				(6" THK) LIGHT WEIGHT CONCRETE W/ CIP 6x6 - W4xW4 WWF	0.33	CY						
				Subtotal								

#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	LABOR			MATERIAL (\$Per Unit)	EQUIPMENT (\$Per Unit)	COMPOSITE RATE/UNIT	TOTAL COST
							MHrs/ Unit	\$/Hour	(\$Per Unit)				
161	S3-101	C4/SS-501		2'Wx1'6"H CONCRETE FOOTING									
162				Compaction of sub-grade.	110	SF							
163				Rebar's (Grade 60)	0.105	TON							
				Concrete footing. (fc = 4000 PSI)	5.60	CY							
164	S3-101	B3/S3-501		2'Wx2'H CONCRETE FOOTING									
165				Compaction of sub-grade.	50	SF							
166				Rebar's (Grade 60)	0.064	TON							
				Concrete footing. (fc = 4000 PSI)	3.40	CY							
167	S3-101	A4/SS-501		5'6"Wx1'6"H CONCRETE FOOTING									
168				Compaction of sub-grade.	45	SF							
169				Rebar's (Grade 60)	0.052	TON							
				Concrete footing. (fc = 4000 PSI)	2.51	CY							
170	S3-101	D1/SS-501		9'Wx2'H CONCRETE FOOTING									
171				Compaction of sub-grade.	85	SF							
172				Rebar's (Grade 60)	0.141	TON							
				Concrete footing. (fc = 4000 PSI)	6.85	CY							
173	S3-101	D1/SS-501		15'Wx2'H CONCRETE FOOTING									
174				Compaction of sub-grade.	470	SF							
175				Rebar's (Grade 60)	0.883	TON							
				Concrete footing. (fc = 4000 PSI)	38.58	CY							
176	S3-101	D2/S-006		1'3"Wx3'H CONCRETE PEDESTAL									
177				Compaction of sub-grade.	30	SF							
178				Rebar's (Grade 60)	0.048	TON							
				Concrete footing. (fc = 4000 PSI)	2.38	CY							
179	S3-101	B4/S3-501		11' SQ.x2'H CONCRETE FOOTING PAD (1 EA)									
180				Compaction of sub-grade.	135	SF							
181				Rebar's (Grade 60)	0.303	TON							
				Concrete footing. (fc = 4000 PSI)	10.31	CY							
182	S3-101	B4/S3-501		ELLIPTICAL SHAPE CONCRETE COLUMN (1 EA)									
183				Rebar's (Grade 60)	0.117	TON							
				Concrete column. (fc = 4000 PSI)	2.34	CY							
184	S3-102	B4/S3-501		3'Wx1'6"H COLUMN CAP (1 EA)									
185				Rebar's (Grade 60)	0.050	TON							
				Concrete column cap. (fc = 4000 PSI)	1.23	CY							
186	S3-102	B4/S3-502		1'Wx1'6"H CONCRETE BEAM									
187				Rebar's (Grade 60)	0.431	TON							
				Concrete beam. (fc = 4000 PSI)	10.50	CY							
188	S3-101	A4/SS-501, C4/SS-501 & D1/SS-501		RETAINING WALL									
189				Rebar's (Grade 60)	0.870	TON							
190				6" THK Retaining wall. (fc = 4000 PSI)	0.37	CY							
191				8" THK Retaining wall. (fc = 4000 PSI)	5.74	CY							
192				10" THK Retaining wall. (fc = 4000 PSI)	26.74	CY							
				KEYWAY	141.60	LF							
193	S3-501			SHOTCRETE WALL									
194				Rebar's (Grade 60)	0.020	TON							
				3" THK Concrete shotcrete wall. (fc = 4000 PSI)	1.17	CY							
195	S3-101	A3/S-003		SLAB ON GRADE									
196				Compaction of subgrade.	120	SF							
197				Vapor barrier.	120	SF							
198				4" THK Aggregate base.	1.44	CY							
199				Rebar's (Grade 60)	0.09	TON							
200				6" THK Concrete slab on grade. (fc = 4000 PSI)	2.34	CY							
				3/4"DIAx15"H EMBEDDED STEEL ROD	4.00	EA							
201	S3-102	D1/S3-501 & B4/S3-502		CONCRETE SLAB									
202				Rebar's (Grade 60)	0.64	TON							
203				6" THK Concrete slab. (fc = 4000 PSI)	16.15	CY							
				6" THK Concrete slab. (fc = 4000 PSI)	1.10	CY							
				Subtotal									

S#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY.	UNIT	LABOR			MATERIAL (\$Per Unit)	EQUIPMENT (\$Per Unit)	COMPOSITE RATE/UNIT	TOTAL COST
							MHrs/ Unit	\$/Hour	(\$Per Unit)				
			030000	DIVISION 03 - CONCRETE									
			033000	CAST IN PLACE CONCRETE									
231	SF2-101	D1/S-003		(1'Wx2'H) CONCRETE FOOTING									
232				Compaction of sub-grade.	80	SF							
233				Rebar's (Grade 60)	0.085	TON							
234				Concrete footing. (fc = 4000 PSI)	4.51	CY							
				WATER STOP	52.91	LF							
235	SF2-101	A2 & C1/S-003		(2'Wx1'6"H) CONCRETE FOOTING									
236				Compaction of sub-grade.	535	SF							
237				Rebar's (Grade 60)	0.511	TON							
238				Concrete footing. (fc = 4000 PSI)	27.21	CY							
				(3/4"DIAx15'H) EMBEDDED STEEL ROD	8.00	EA							
239	SF2-101	A2, C1 & D5/S-003		(8"/12"Wx8"H) THICKEND EDGE CONCRETE SLAB FOOTING									
240				Compaction of sub-grade.	335	SF							
241				Rebar's (Grade 60)	0.127	TON							
				Concrete footing. (fc = 4000 PSI)	6.77	CY							
242	SF2-101	S-002		SLAB ON GRADE									
243				Compaction of subgrade.	720	SF							
244				Vapor barrier.	720	SF							
245				(4" THK) Aggregate base.	8.88	CY							
246				Rebar's (Grade 60)	0.54	TON							
				(5" THK) Concrete slab on grade. (fc = 4000 PSI)	12.20	CY							
				Subtotal									
			020000	DIVISION 02 - EXISTING CONDITIONS									
			022000	EARTHWORK									
247	SF2-101			Footing excavation.	5.69	CY							
248				Footing backfill.	1.22	CY							
				Subtotal									
			030000	DIVISION 03 - CONCRETE									
			033000	CAST IN PLACE CONCRETE									
249	SF2-101	C1-S003		(2'Wx1'6"H) CONCRETE FOOTING									
250				Compaction of sub-grade.	90	SF							
251				Rebar's (Grade 60)	0.083	TON							
				Concrete footing. (fc = 4000 PSI)	4.40	CY							
252	SF2-101	C1-S003		(8"/12"Wx8"H) THICKEND EDGE CONCRETE SLAB FOOTING									
253				Compaction of sub-grade.	40	SF							
254				Rebar's (Grade 60)	0.014	TON							
				Concrete footing. (fc = 4000 PSI)	0.75	CY							
255	SF2-101	S-002		SLAB ON GRADE									
256				Compaction of subgrade.	65	SF							
257				Vapor barrier.	65	SF							
258				(4" THK) Aggregate base.	0.80	CY							
259				Rebar's (Grade 60)	0.05	TON							
				(5" THK) Concrete slab on grade. (fc = 4000 PSI)	1.10	CY							
				Subtotal									
			020000	DIVISION 02 - EXISTING CONDITIONS									
			022000	EARTHWORK									
260	SF2-103			Footing excavation.	54.08	CY							
261				Footing backfill.	13.63	CY							
				Subtotal									
			030000	DIVISION 03 - CONCRETE									
			033000	CAST IN PLACE CONCRETE									
262	SF2-103	D1/S-003		(1'Wx2'H) CONCRETE FOOTING									
263				Compaction of sub-grade.	175	SF							
264				Rebar's (Grade 60)	0.185	TON							
265				Concrete footing. (fc = 4000 PSI)	9.86	CY							
				KEYWAY	115.74	LF							
266	SF2-103	C1-S003		(2'Wx1'6"H) CONCRETE FOOTING									
267				Compaction of sub-grade.	500	SF							
268				Rebar's (Grade 60)	0.478	TON							
				Concrete footing. (fc = 4000 PSI)	25.48	CY							
269	SF2-103	C1-S003		(8"/12"Wx8"H) THICKEND EDGE CONCRETE SLAB FOOTING									
270				Compaction of sub-grade.	440	SF							
271				Rebar's (Grade 60)	0.167	TON							
				Concrete footing. (fc = 4000 PSI)	8.87	CY							
272	SF2-103	A1/S-003		(3' SQ.x1'6"H) CONCRETE FOOTING PAD (4 EA)									
273				Compaction of sub-grade.	50	SF							
274				Rebar's (Grade 60)	0.043	TON							
275				Concrete footing. (fc = 4000 PSI)	2.30	CY							
				(3/4"DIAx15'H) EMBEDDED STEEL ROD	16.00	EA							
276	SF2-103	S-002		SLAB ON GRADE									
277				Compaction of subgrade.	2500	SF							
278				Vapor barrier.	2500	SF							
279				(4" THK) Aggregate base.	30.78	CY							
280				Rebar's (Grade 60)	1.87	TON							
				(5" THK) Concrete slab on grade. (fc = 4000 PSI)	42.30	CY							
				Subtotal									
			020000	DIVISION 02 - EXISTING CONDITIONS									
			022000	EARTHWORK									
281	SK1-101			Footing excavation.	108.49	CY							
282				Footing backfill.	20.56	CY							
				Subtotal									
			030000	DIVISION 03 - CONCRETE									
			033000	CAST IN PLACE CONCRETE									
283	SK1-101	D1/S-003		(1'Wx2'H) CONCRETE FOOTING									
284				Compaction of sub-grade.	30	SF							
285				Rebar's (Grade 60)	0.032	TON							
286				Concrete footing. (fc = 4000 PSI)	1.68	CY							
				WATER STOP	19.75	LF							
287	SK1-101	A2/S-003		(1'6"Wx1'6"H) CONCRETE FOOTING									
288				Compaction of sub-grade.	135	SF							
289				Rebar's (Grade 60)	0.118	TON							
				Concrete footing. (fc = 4000 PSI)	6.30	CY							
290	SK1-101	A2/S-003		(2'Wx1'6"H) CONCRETE FOOTING									
291				Compaction of sub-grade.	280	SF							
292				Compaction of sub-grade.	0.268	TON							
				Concrete footing. (fc = 4000 PSI)	14.26	CY							
293	SK1-101	A4/SK-502		(3'4"Wx1'4"H) CONCRETE FOOTING									
294				Compaction of sub-grade.	70	SF							
295				Compaction of sub-grade.	0.063	TON							
				Concrete footing. (fc = 4000 PSI)	3.35	CY							
296	SK1-101	B4 & D4/SS-502		(4'Wx1'6"H) CONCRETE FOOTING									
297				Compaction of sub-grade.	405	SF							
				Compaction of sub-grade.	0.428	TON							

#	DWG #	DETAIL #	CSI NO	DESCRIPTION	QTY	UNIT	LABOR			MATERIAL	EQUIPMENT	COMPOSITE	TOTAL
							MHrs/ Unit	\$/Hour	(\$Per Unit)	(\$Per Unit)	(\$Per Unit)	RATE/UNIT	COST
298				Concrete footing, (fc = 4000 PSI)	22.81	CY							
299				(1"DIAx12"H) EMBEDDED STEEL ROD	16.00	EA							
300	SK1-101	A4/SK-502		(7"Wx16"H) CONCRETE FOOTING									
301				Compaction of sub-grade.	135	SF							
302				Compaction of sub-grade.	0.163	TON							
				Concrete footing, (fc = 4000 PSI)	7.92	CY							
303	SK1-101	A2/S-003		(8"12"Wx8"H) THICKEND EDGE CONCRETE SLAB FOOTING									
304				Compaction of sub-grade.	260	SF							
305				Rebar's (Grade 60)	0.099	TON							
				Concrete footing, (fc = 4000 PSI)	5.25	CY							
306	SK1-101	B1/S-009 & 5/SK-301		(2'3"Wx8"H) THICKEND EDGE CONCRETE SLAB FOOTING									
307				Compaction of sub-grade.	50	SF							
308				Rebar's (Grade 60)	0.022	TON							
				Concrete footing, (fc = 4000 PSI)	1.16	CY							
309	SK1-101	B1/S-009 & 5/SK-301		(2'6"Wx2'H) CONCRETE GRADE BEAM									
310				Compaction of sub-grade.	50	SF							
311				Rebar's (Grade 60)	0.071	TON							
				Concrete footing, (fc = 4000 PSI)	3.48	CY							
312	SK1-101	D4& D5/S007 & B1/S-009		(4' SQ.x1'6"H) CONCRETE FOOTING PAD (2 EA)									
313				Compaction of sub-grade.	40	SF							
314				Rebar's (Grade 60)	0.038	TON							
315				Concrete footing, (fc = 4000 PSI)	2.04	CY							
				(3/4"DIAx15"H) EMBEDDED STEEL ROD	8.00	EA							
316	SK1-101	D4& D5/S007 & B1/S-009		(5' SQ.x2'H) CONCRETE FOOTING PAD (2 EA)									
317				Compaction of sub-grade.	60	SF							
318				Rebar's (Grade 60)	0.113	TON							
319				Concrete footing, (fc = 4000 PSI)	4.26	CY							
				(1"DIAx30"H) EMBEDDED STEEL ROD	8.00	EA							
320	SK1-101	D4& D5/S007 & B1/S-009		(6' SQ.x3'H) CONCRETE FOOTING PAD (2 EA)									
321				Compaction of sub-grade.	60	SF							
322				Rebar's (Grade 60)	0.169	TON							
323				Concrete footing, (fc = 4000 PSI)	6.39	CY							
				(1"DIAx30"H) EMBEDDED STEEL ROD	12.00	EA							
324	SK1-101	B4 & D4/SS-502		CONCRETE WALL									
325				Rebar's (Grade 60)	0.590	TON							
326				(18" THK) Concrete wall, (fc = 4000 PSI)	22.23	CY							
				KEYWAY	77.32	LF							
327	SK1-101			CONCRETE SEAT WALL									
328				Rebar's (Grade 60)	0.150	TON							
329				(2'4"Wx2'10"H) Concrete seat wall, (fc = 4000 PSI)	1.83	CY							
				(3'4"Wx2'10"H) Concrete seat wall, (fc = 4000 PSI)	5.63	CY							
330	SK1-101			(15"THKx3'6"H) CONCRETE BENCH									
331				Rebar's (Grade 60)	0.060	TON							
				(15"THKx3'6"H) Concrete bench, (fc = 4000 PSI)	2.96	CY							
332	SK1-101	S-002		SLAB ON GRADE									
333				Compaction of subgrade.	1230	SF							
334				Vapor barrier.	1230	SF							
335				(4" THK) Aggregate base.	15.16	CY							
336				Rebar's (Grade 60)	0.92	TON							
				(6" THK) Concrete slab on grade, (fc = 4000 PSI)	24.66	CY							
337	SK1-101	S-002		EXTERIOR SLAB ON GRADE									
338				Compaction of subgrade.	2475	SF							
339				Vapor barrier.	2475	SF							
340				(4" THK) Aggregate base.	30.51	CY							
341				Rebar's (Grade 60)	3.86	TON							
				(6" THK) Concrete slab on grade, (fc = 4000 PSI)	49.62	CY							
342	SK1-101	A4/SK-501		LIGHT WEIGHT CONCRETE SLAB									
				(2-1/2" THK) LIGHT WEIGHT CONCRETE W/ CIP 6x6 - W4xW4 WWF	2.75	CY							
				Subtotal									
		</											

[illegible]

(6"/1'3"Wx1'H) THICKEND EDGE CONCRETE SLAB FOOTING	S5-103	1	1	1.375	31.08	1	0.875	31.08	0.00	0.00	0.00	31.08	31.08	1.58	0.58	0.022	1.01	0.15	1.16
BUILDING 800																			
(8"/12"Wx8"H) THICKEND EDGE CONCRETE SLAB FOOTING	S8-101	1	0.666	1.166	159.86	0.666	0.833	159.86	0.00	0.00	0.00	106.47	159.86	4.60	1.31	0.071	3.28	0.49	3.78
SOFTBALL FIELDS DUGOUT																			
(1'Wx2'H) CONCRETE FOOTING	SF2-101	1	2	1.5	52.91	2	1	52.91	0.00	0.00	52.91	211.64	52.91	5.88	1.96	0.085	3.92	0.59	4.51
(2'Wx1'6"H) CONCRETE FOOTING W/ (3/4"DIAx15"H) EMBEDDED STEEL ROD		1	1.5	2.5	212.96	1.5	2	212.96	8.00	0.00	0.00	638.88	212.96	29.58	5.92	0.511	23.66	3.55	27.21
(8"/12"Wx8"H) THICKEND EDGE CONCRETE SLAB FOOTING		1	0.666	1.166	286.56	0.666	0.833	286.56	0.00	0.00	0.00	190.85	286.56	8.24	2.35	0.127	5.89	0.88	6.77
SOFTBALL FIELDS SCOREKEEPER																			
(2'Wx1'6"H) CONCRETE FOOTING	SF2-101	1	1.5	2.5	34.41	1.5	2	34.41	0.00	0.00	0.00	103.23	34.41	4.78	0.96	0.083	3.82	0.57	4.40
(8"/12"Wx8"H) THICKEND EDGE CONCRETE SLAB FOOTING		1	0.666	1.166	31.74	0.666	0.833	31.74	0.00	0.00	0.00	21.14	31.74	0.91	0.26	0.014	0.65	0.10	0.75
ATHLETIC FIELDS RESTROOMS & CONCESSIONS																			
(1'Wx2'H) CONCRETE FOOTING	SF2-103	1	2	1.5	115.74	2	1	115.74	0.00	115.74	0.00	462.96	115.74	12.86	4.29	0.185	8.57	1.29	9.86
(2'Wx1'6"H) CONCRETE FOOTING		1	1.5	2.5	199.42	1.5	2	199.42	0.00	0.00	0.00	598.26	199.42	27.70	5.54	0.479	22.16	3.32	25.48
(8"/12"Wx8"H) THICKEND EDGE CONCRETE SLAB FOOTING		1	0.666	1.166	375.46	0.666	0.833	375.46	0.00	0.00	0.00	250.06	375.46	10.80	3.08	0.167	7.71	1.16	8.87
KIOSK 1																			
(1'Wx2'H) CONCRETE FOOTING	SK1-101	1	2	1.5	19.75	2	1	19.75	0.00	0.00	19.75	79.00	19.75	2.19	0.73	0.032	1.46	0.22	1.68
(1'6"Wx1'6"H) CONCRETE FOOTING		1	1.5	2	65.73	1.5	1.5	65.73	0.00	0.00	0.00	197.19	65.73	7.30	1.83	0.118	5.48	0.82	6.30
(2'Wx1'6"H) CONCRETE FOOTING		1	1.5	2.5	111.58	1.5	2	111.58	0.00	0.00	0.00	334.74	111.58	15.50	3.10	0.268	12.40	1.86	14.26
(3'4"Wx1'4"H) CONCRETE FOOTING		1	1.333	3.833	17.71	1.333	3.333	17.71	0.00	0.00	0.00	47.21	17.71	3.35	0.44	0.063	2.91	0.44	3.35
(4'Wx1'6"H) CONCRETE FOOTING W/ (1"DIAx12"H) EMBEDDED STEEL ROD		1	1.5	4.5	89.26	1.5	4	89.26	16.00	0.00	0.00	267.78	89.26	22.32	2.48	0.428	19.84	2.98	22.81
(7'Wx1'6"H) CONCRETE FOOTING		1	1.5	7.5	17.71	1.5	7	17.71	0.00	0.00	0.00	53.13	17.71	7.38	0.49	0.163	6.89	1.03	7.92
(8"/12"Wx8"H) THICKEND EDGE CONCRETE SLAB FOOTING		1	0.666	1.166	222.14	0.666	0.833	222.14	0.00	0.00	0.00	147.95	222.14	6.39	1.82	0.099	4.56	0.68	5.25
(2'/3"Wx8"H) THICKEND EDGE CONCRETE SLAB FOOTING		1	0.666	3	16.29	0.666	2.5	16.29	0.00	0.00	0.00	10.85	16.29	1.21	0.20	0.022	1.00	0.15	1.16
(2'6"Wx2'H) CONCRETE GRADE BEAM		1	2	3	16.32	2	2.5	16.32	0.00	0.00	0.00	65.28	16.32	3.63	0.60	0.071	3.02	0.45	3.48
KIOSK 3																			
(1'Wx2'H) CONCRETE FOOTING	SK3-101	1	2	1.5	47.17	2	1	47.17	0.00	0.00	47.17	188.68	47.17	5.24	1.75	0.075	3.49	0.52	4.02
(2'Wx1'6"H) CONCRETE FOOTING		1	1.5	2.5	50.95	1.5	2	50.95	0.00	0.00	0.00	152.85	50.95	7.08	1.42	0.122	5.66	0.85	6.51
(3'4"Wx1'4"H) CONCRETE FOOTING		1	1.333	3.833	17.7	1.333	3.333	17.7	0.00	0.00	17.70	47.19	17.70	3.35	0.44	0.063	2.91	0.44	3.35
(7'Wx1'6"H) CONCRETE FOOTING		1	1.5	7.5	12.71	1.5	7	12.71	0.00	0.00	0.00	38.13	12.71	5.30	0.35	0.117	4.94	0.74	5.68
(8"/12"Wx8"H) THICKEND EDGE CONCRETE SLAB FOOTING		1	0.666	1.166	125.14	0.666	0.833	125.14	0.00	0.00	0.00	83.34	125.14	3.60	1.03	0.056	2.57	0.39	2.96
(2'/3"Wx8"H) THICKEND EDGE CONCRETE SLAB FOOTING		1	0.666	3	18.16	0.666	2.5	18.16	0.00	0.00	0.00	12.09	18.16	1.34	0.22	0.024	1.12	0.17	1.29
(2'6"Wx2'H) CONCRETE GRADE BEAM		1	2	3	18.3	2	2.5	18.3	0.00	0.00	0.00	73.20	18.30	4.07	0.68	0.080	3.39	0.51	3.90
SITEWORK																			
(3'6"Wx1'H) CONCRETE BENCH FOOTING	AS-110 to AS-129	1	1	4	368.78	1	3.5	368.78	0.00	0.00	0.00	737.56	368.78	54.63	6.83	1.033	47.80	7.17	54.98
(2'Wx1'H) CONCRETE QUAD SEAT FOOTING		1	1	2.5	395.01	1	2	395.01	0.00	0.00	0.00	790.02	395.01	36.58	7.32	0.632	29.26	4.39	33.65
(10"Wx1'4"H) STAIR CONCRETE FOOTING		1	1.333	1.333	45.17	1.333	0.833	45.17	0.00	0.00	0.00	120.42	45.17	2.97	1.12	0.040	1.86	0.28	2.14

(2'6"Wx2'10"H) CONCRETE BENCH				1	2.833	3	417.94	2.833	2.5	417.94	0.00	0.00	0.00	2368.05	417.94	131.56	21.93	2.590	109.63	16.44	126.08
												0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.000	0.00	0.00
											64.0	127.9	137.5	13478.4	5226.7	738.6	126.0	14.0	612.6	91.9	704.5
															TOTAL FOOTING CONCRETE					704.5	



ESTIMATOR ----->																						
ESTIMATE DESCRIPTION -->																						
ARCHITECT ----->																						
PLAN DATE ----->																						
CONTACT PERSON ----->																						
PHONE NUMBER ----->																						
MISC INFORMATION																						
PAD FTG			CONCRETE PSI	4000					DATE													
DESCRIPTION	DWG NO.	QUANT.	EXCAVATION QTY				CONCRETE QTY				EMBEDED STEEL	KEYWAY	WATER STOP	FORM	LAYOUT	EXCAV.	BACKFILL	REBAR	POUR CONC.	15% WASTE	TOTAL CONC.	
			DIA	DEPTH	WIDTH	LENGTH	DIA	DEPTH	WIDTH	LENGTH												
		EA		LF	LF	LF		LF	LF	LF	EA	LF	LF	SFCA	LF	CY	CY	TON	CY	CY	CY	
BUILDING 100																						
(3' SQ.x1'6"H) CONCRETE FOOTING PAD W/ (3/4"DIAx15"H) EMBEDDED STEEL ROD	S1-101	5		1.5	3.5	3.5		1.5	3	3	20.00	0.00	0.00	90.00	60.00	3.40	0.90	0.054	2.50	0.38	2.88	
(4' SQ.x1'6"H) CONCRETE FOOTING PAD W/ (3/4"DIAx15"H) EMBEDDED STEEL ROD		1		1.5	4.5	4.5		1.5	4	4	4.00	0.00	0.00	24.00	16.00	1.13	0.24	0.019	0.89	0.13	1.02	
(5' SQ.x2"H) CONCRETE FOOTING PAD W/ (3/4"DIAx15"H) EMBEDDED STEEL ROD		1		2	5.5	5.5		2	5	5	4.00	0.00	0.00	40.00	20.00	2.24	0.39	0.056	1.85	0.28	2.13	
(5"Wx6"Lx2"H) CONCRETE FOOTING PAD W/ (3/4"DIAx15"H) EMBEDDED STEEL ROD		1		2	5.5	6.5		2	5	6	8.00	0.00	0.00	44.00	22.00	2.65	0.43	0.068	2.22	0.33	2.56	
(8'8"Wx9'7"Lx1'2"H) ELEVATOR CONCRETE FOOTING PAD W/ (5/8"DIAx12"H) EMBEDDED STEEL ROD		1		1.166	9.166	10.083		1.166	8.666	9.583	8.00	0.00	0.00	42.56	36.50	3.99	0.40	0.109	3.59	0.54	4.12	
BUILDING 300																						
(11' SQ.x2"H) CONCRETE FOOTING PAD	S3-101	1		2	11.5	11.5		2	11	11	0.00	0.00	0.00	88.00	44.00	9.80	0.83	0.303	8.96	1.34	10.31	
BUILDING 500																						
(3' DIAx7'6"D) DRILLED PIER FOOTING W/ (7/8"DIAx48"H) EMBEDDED STEEL ROD	S5-103	8	3.5	7.5	0	0	3	7.5	0	0	64.00	0.00	0.00	565.56	75.41	2.67	0.71	0.477	15.71	2.36	18.07	
BUILDING 800																						
(6" THK) CONCRETE EQUIPMENT PAD W/ (3/8"DIAx2"H) EMBEDDED STEEL ROD	S8-101	4		0.5	6.333	14.666		0.5	5.833	14.166	32.00	0.00	0.00	80.00	159.99	6.88	0.76	0.132	6.12	0.92	7.04	
ATHLETIC FIELDS RESTROOMS & CONCESSIONS																						
(3' SQ.x1'6"H) CONCRETE FOOTING PAD W/ (3/4"DIAx15"H) EMBEDDED STEEL ROD	SF2-103	4		1.5	3.5	3.5		1.5	3	3	16.00	0.00	0.00	72.00	48.00	2.72	0.72	0.043	2.00	0.30	2.30	
KIOSK 1																						
(4' SQ.x1'6"H) CONCRETE FOOTING PAD W/ (3/4"DIAx15"H) EMBEDDED STEEL ROD	SK1-101	2		1.5	4.5	4.5		1.5	4	4	8.00	0.00	0.00	48.00	32.00	2.25	0.47	0.038	1.78	0.27	2.04	
(5' SQ.x2"H) CONCRETE FOOTING PAD W/ (1"DIAx30"H) EMBEDDED STEEL ROD		2		2	5.5	5.5		2	5	5	8.00	0.00	0.00	80.00	40.00	4.48	0.78	0.113	3.70	0.56	4.26	
(5' SQ.x3"H) CONCRETE FOOTING PAD W/ (1"DIAx30"H) EMBEDDED STEEL ROD		2		3	5.5	5.5		3	5	5	12.00	0.00	0.00	120.00	40.00	6.72	1.17	0.169	5.56	0.83	6.39	
KIOSK 3																						
(5' SQ.x2"H) CONCRETE FOOTING PAD W/ (1"DIAx30"H) EMBEDDED STEEL ROD		2		2	5.5	5.5		2	5	5	8.00	0.00	0.00	80.00	40.00	4.48	0.78	0.113	3.70	0.56	4.26	
SITEWORK																						
(6" THK) CONCRETE BACKFLOW PREVENTION PAD	C-141	1		0.5	6.5	11.25		0.5	6	10.75	0.00	0.00	0.00	21.50	33.50	1.35	0.16	0.026	1.19	0.18	1.37	
											192.0	0.0	0.0	1395.6	667.4	54.8	8.7	1.7	59.8	9.0	68.7	
														TOTAL FOOTING CONCRETE							68.7	

	MISC INFORMATION
--	------------------

COLUMN & BEAM			CONCRETE PSI		4000	DATE							
DESCRIPTION	DWG NO.	QUANT.	CONCRETE QTY			FORM	LAYOUT	REBAR	POUR CONC.	15% WASTE	TOTAL CONC.		
			DEPTH	WIDTH	LENGTH								
		EA	LF	LF	LF	SFCA	LF	TON	CY	CY	CY		
BUILDING 300													
ELLIPTICAL SHAPE CONCRETE COLUMN			S3-101	1	10	5.5	86.90	5.50	0.117	2.04	0.31	2.34	
(3'Wx1'6"H) COLUMN CAP			S3-102	1	1.5	3	6.4	38.40	6.40	0.050	1.07	0.16	1.23
(1'Wx1'6"H) CONCRETE BEAM				1	1.5	1	164.29	657.16	164.29	0.431	9.13	1.37	10.50
							0.00	0.00	0.000	0.00	0.00	0.00	
							782.5	176.2	0.6	12.2	1.8	14.1	
							TOTAL WALL CONCRETE					14.1	

ESTIMATOR ----->																			
ESTIMATE DESCRIPTION -->																			
ARCHITECT ----->																			
PLAN DATE ----->																			
CONTACT PERSON ----->																			
PHONE NUMBER ----->																			
MISC INFORMATION																			
WALL		CONCRETE PSI		4000		DATE													
DESCRIPTION	DWG NO.	QUANT.	EXCAVATION QTY			CONCRETE QTY			EMBEDDED STEEL	KEYWAY	WATER STOP	FORM	LAYOUT	EXCAV.	BACKFILL	REBAR	POUR CONC.	15% WASTE	TOTAL CONC.
			DEPTH	WIDTH	LENGTH	DEPTH	WIDTH	LENGTH											
		EA	LF	LF	LF	LF	LF	EA	LF	LF	SFCA	LF	CY	CY	TON	CY	CY	CY	
BUILDING 100																			
(6" THK) RETAINING WALL	S1-101	1	1.666	1.5	738.65	1.666	0.5	738.65	0.00	0.00	0.00	2461.18	738.65	68.37	45.58	0.538	22.79	3.42	26.21
(8" THK) RETAINING WALL		1	3.5	7.5	35.51	3.5	0.666	35.51	0.00	0.00	0.00	248.57	35.51	34.52	31.46	0.093	3.07	0.46	3.53
(10" THK) RETAINING WALL		1	5.5	7.5	65.35	5.5	0.833	65.35	0.00	65.35	0.00	718.85	65.35	99.84	88.75	0.337	11.09	1.66	12.75
(12" THK) RETAINING WALL		1	1.666	1.5	116.88	1.666	1	116.88	0.00	0.00	0.00	389.44	116.88	10.82	3.61	0.219	7.21	1.08	8.29
(18" THK) RETAINING WALL		1	4	7	87.72	4	1.5	87.72	0.00	87.72	0.00	701.76	87.72	90.97	71.48	0.658	19.49	2.92	22.42
(6" THK) SHOTCRETE WALL	S1-101 & S-403	1	0	0	0	13	0.5	97	0.00	0.00	0.00	1261.00	97.00	0.00	0.00	0.709	23.35	3.50	26.85
(8" THK) SHOTCRETE WALL		1	0	0	0	13	0.666	7.39	0.00	0.00	0.00	96.07	7.39	0.00	0.00	0.072	2.37	0.36	2.73
BUILDING 300																			
(6" THK) RETAINING WALL	S3-101	1	3	2.5	5.82	3	0.5	5.82	0.00	5.82	0.00	34.92	5.82	1.62	1.29	0.008	0.32	0.05	0.37
(8" THK) RETAINING WALL		1	3.5	2.5	57.8	3.5	0.666	57.8	0.00	57.80	0.00	404.60	57.80	18.73	13.74	0.152	4.99	0.75	5.74
(10" THK) RETAINING WALL		1	9.666	1.333	77.98	9.666	0.833	77.98	0.00	77.98	0.00	1507.51	77.98	37.21	13.96	0.706	23.25	3.49	26.74
(3" THK) SHOTCRETE WALL	S3-501	1	0	0	0	7.333	0.25	15	0.00	0.00	0.00	110.00	15.00	0.00	0.00	0.022	1.02	0.15	1.17
BUILDING 500																			
(2'Wx2'10"H) CONCRETE SEAT WALL	S5-103	1	0	0	0	2.833	2	62.93	0.00	0.00	0.00	356.56	62.93	0.00	0.00	0.312	13.21	1.98	15.19
KIOSK 1																			
(18" THK) CONCRETE WALL	SK1-101	1	4.5	2	77.32	4.5	1.5	77.32	0.00	77.32	0.00	695.88	77.32	25.77	6.44	0.587	19.33	2.90	22.23
(2'4"Wx2'10"H) CONCRETE SEAT WALL		1	0	0	0	2.833	2.333	6.5	0.00	0.00	0.00	36.83	6.50	0.00	0.00	0.038	1.59	0.24	1.83
(3'4"Wx2'10"H) CONCRETE SEAT WALL		1	0	0	0	2.833	3.333	14	0.00	0.00	0.00	79.32	14.00	0.00	0.00	0.116	4.90	0.73	5.63
(15"THKx3'6"H) CONCRETE BENCH		1	0	0	0	3.5	1.25	15.86	0.00	0.00	0.00	111.02	15.86	0.00	0.00	0.061	2.57	0.39	2.96
SITework																			
(6"THKx1'8"H) CONCRETE BENCH WALL	AS-110 to QTO-1301-SAN DIEGO HIGH SCHOOL	1	0.833	0.5	86.37	1.666	0.5	86.37	0.00	0.00	0.00	287.78	86.37	1.33	0.00	0.068	2.66	0.40	3.06
(7"THKx1'8"H) CONCRETE BENCH WALL		1	0.833	0.583	528.69	1.666	0.583	528.69	0.00	0.00	0.00	1761.60	528.69	9.51	0.00	0.488	19.02	2.85	21.87
(8"THKx1'8"H) CONCRETE BENCH WALL		1	0.833	0.666	116.35	1.666	0.666	116.35	0.00	0.00	0.00	387.68	116.35	2.39	0.00	0.123	4.78	0.72	5.50
(6"THKx1'H) CONCRETE QUAD SEAT WALL		1	0.833	0.5	43.47	1	0.5	43.47	0.00	0.00	0.00	86.94	43.47	0.67	0.00	0.021	0.81	0.12	0.93

DESCRIPTION			DWG NO.	QUANT.	EXCAVATION QTY			CONCRETE QTY			EMBEDDED STEEL	KEYWAY	WATER STOP	FORM	LAYOUT	EXCAV.	BACKFILL	REBAR	POUR CONC.	15% WASTE	TOTAL CONC.		
					DEPTH	WIDTH	LENGTH	DEPTH	WIDTH	LENGTH													
					EA	LF	LF	LF	LF	LF												EA	LF
(6"THKx1'8"H) CONCRETE QUAD SEAT WALL			AS-129	1	0.833	0.5	43.99	1.666	0.5	43.99	0.00	0.00	0.00	146.57	43.99	0.68	0.00	0.035	1.36	0.20	1.56		
(6"THKx2'3"H) CONCRETE QUAD SEAT WALL				1	0.833	0.5	45.32	2.25	0.5	45.32	0.00	0.00	0.00	203.94	45.32	0.70	0.00	0.048	1.89	0.28	2.17		
(8"THKx2'H) CONCRETE QUAD SEAT WALL				1	0.833	0.666	148.25	2	0.666	148.25	0.00	0.00	0.00	593.00	148.25	3.05	0.00	0.188	7.31	1.10	8.41		
(8"THKx4'H) CONCRETE QUAD SEAT WALL				1	0.833	0.666	157.45	4	0.666	157.45	0.00	0.00	0.00	1259.60	157.45	3.24	0.00	0.398	15.54	2.33	17.87		
											0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00		
											0.0	372.0	0.0	13940.6	2651.6	409.4	276.3	6.0	213.9	32.1	246.0		
													TOTAL WALL CONCRETE										246.0

ESTIMATOR ----->											
ESTIMATE DESCRIPTION -->											
ARCHITECT ----->											
PLAN DATE ----->											
CONTACT PERSON ----->											
PHONE NUMBER ----->											
MISC INFORMATION											
SLAB											
CONCRETE PSI 4000											
DESCRIPTION	DWG NO.	QUANT.	SLAB			EDGE FORM	CUBIC YARD	WASTE 1/2"	FINISH SLAB	REBAR	POUR CONC.
			SLAB PERIMETER	SLAB DEPTH	SLAB CONC.						
		EA	LF	LF	SF	SF	CY	CY	SF	TON	CY
BUILDING 100											
(2" THK) LIGHT WEIGHT CONCRETE W/ CIP 6x6 - W4xW4 WWF	S1-102	1	140	0.166	361.92	23.24	2.23	0.56	361.92	0.000	2.78
(6" THK) LIGHT WEIGHT CONCRETE W/ CIP 6x6 - W4xW4 WWF	S1-102	1	20	0.5	16.63	10.00	0.31	0.03	16.63	0.000	0.33
BUILDING 300											
(6" THK) CONCRETE SLAB	S3-102	1	240	0.5	805.05	120.00	14.91	1.24	805.05	0.604	16.15
(8" THK) CONCRETE SLAB		1	27	0.666	41.9	17.98	1.03	0.06	41.90	0.031	1.10
KIOSK 1											
(2-1/2" THK) LIGHT WEIGHT CONCRETE W/ CIP 6x6 - W4xW4 WWF	SK1-101	1	73	0.2	307.58	14.60	2.28	0.47	307.58	0.000	2.75
SITework											
(6"THK) CONCRETE BENCH SEAT	AS-110 to AS-129	1	260	0.5	304.27	130.00	5.63	0.47	304.27	0.228	6.10
(8"THK) CONCRETE BENCH SEAT		1	580	0.666	1244.85	386.28	30.71	1.92	1244.85	0.934	32.63
(8"THK) CONCRETE QUAD SEAT		1	345	0.666	999.26	229.77	24.65	1.54	999.26	0.749	26.19


```
ESTIMATOR ----->
ESTIMATE DESCRIPTION -->
ARCHITECT ----->
PLAN DATE ----->
CONTACT PERSON ----->
PHONE NUMBER ----->
```

MISC INFORMATION

CURBS & GUTTERS			CONCRETE PSI			4000			DATE				
DESCRIPTION OF FOOTING	DWG NO.	QUANT.	CURB			GUTTER			CURB	GUTTER	CUBIC YARD	REBAR	TOTAL CONC.
			DEPTH	WIDTH	LENGTH	DEPTH	WIDTH	LENGTH					
		EA	LF	LF	LF	LF	LF	LF	LF	LF	LF	CY	TON
BUILDING 300													
(6"Wx17"H) CONCRETE CURB		1	1.583	0.5	130.65	0	0	0	130.65	0.00	3.83	0.136	3.83
SITework													
(6"/11"Wx15"H) CONCRETE CURB	C-112 to C-117	1	1.25	0.7	3805.23	0	0	0	3805.23	0.00	123.32	1.984	123.32
(6"Wx15"H) CONCRETE CURB		1	1.25	0.5	5726.82	0	0	0	5726.82	0.00	132.57	2.987	132.57
(2"Wx6"H) CONCRETE GUTTER		1	0	0	0	0.5	2	861.98	0.00	861.98	31.93	0.899	31.93
									0.00	0.00	0.00	0.000	0.00
									9662.7	862.0	291.6	6.0	291.6

TOTAL CURB & GUTTER CONCRETE	291.64
------------------------------	--------

